

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer, Dasarahalli Division

Schedule - B

NAME OF THE WORK: Construction of R C C Drains 6th and 7th cross in Kalalanagar in Ward No.15
(SCP/TSP Works Block No.76)


BBMP/2023-24/OW/WORK_INDENT2626


Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Providing and laying 100mm thick pre-cast cover slabs over Existing Drain using M20 concrete reinforced slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including: of labour, materials, machinery, lead and lift charges etc, Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Sqm	136.31	1748.77	Rupees One Thousand Seven Hundred Forty Eight and Seventy Seven Paise Only
2	Appendix I Additionalities for Formwork, Centering & Scaffolding 3.Foundation, Sub structure of Cross drainages 5% Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	47.71	293.52	Rupees Two Hundred Ninety Three and Fifty Two Paise Only
3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	20.45	5560.19	Rupees Five Thousand Five Hundred Sixty and Nineteen Paise Only

K.P. Sachin
Signature of the Contractor

K.M. H. H. H.
Executive Engineer
Dasarahalli Division

4	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately)M20 Design Mix Using 20 mm and down size graded crushed coarse aggregates Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	47.71	5870.27	Rupees Five Thousand Eight Hundred Seventy and Twenty Seven Paise Only
5	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancillary operations complete as per drawing and technical specification All other type of structures Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	MT	2.15	73353.81	Rupees Seventy Three Thousand Three Hundred Fifty Three and Eighty One Paise Only
6	Earth work excavation by manual means for drains, canals and similar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, re- moval of stumps and other deleterious matter, excavated surface lev- eled and sides neatly dressed disposing off the excavated stuff or sort- ing & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other	Cum	122.67	224.67	Rupees Two Hundred Twenty Four and Sixty Seven Paise Only
7	Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road (Taking output 10 tonnes load and lead 10 km = 100 t.km) Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	1570.18	11.14	Rupees Eleven and Fourteen Paise Only
8	Loading and Unloading of Stone Boulder/ Stone aggregates/Sand/Kankar/Moorum. (Tipper 10 m3) Complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	122.67	110.48	Rupees One Hundred Ten and Forty Eight Paise Only


Signature of the Contractor


Executive Engineer,
Dasarahalli Division,